

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-20835-00-00
Spot: SWNESWNE Sec/Twnshp/Rge: 8-33S-6E
3604 feet from S Section Line, 1867 feet from E Section Line
Lease Name: SHENEMAN Well #: 3
County: COWLEY Total Vertical Depth: 3190 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3190		100 SX
SURF	8.625	200		140 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2017 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: _____ Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL
Date/Time Plugging Completed: 05/25/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:
SET CIBP ON WIRELINE @ 3070', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG.
SET CIBP ON WIRELINE @ 2690'. DUMP BAILED 4 SXS CEMENT ON TOP OF PLUG.
RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 350'-351' (4 HOLES). RIH W/
TUBING @ 352', QES MIXED & PUMPED 180 SXS 60/40 POZMIX 4% GEL 2% CC &
HULS TO SURFACE. CEMENT CIRCULATED. SIP 300#.

Perfs:

Top	Bot	Thru	Comments
3114	3118	CSG	
2720	2726	CSG	

Remarks: CEMENT TICKET #51982

Plugged through: TBG

INVOICED
JUL 12 2017

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

18