

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-40433-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 21-28S-8E  
4921 feet from S Section Line, 4277 feet from E Section Line  
Lease Name: FERRELL Well #: 12  
County: BUTLER Total Vertical Depth: 2748 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2722		1 SX
SURF	12.5	1025		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/20/2017 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: JIM BYERS Company: \_\_\_\_\_ Phone: (620) 672-9001

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/22/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

DUG OUT CELLAR. CEMENT ON BACKSIDE TO SURFACE. RIH WITH WIRELINE. SET CIBP @ 2670', DUMP BAILED 4 SXS CEMENT ON TOP OF PLUG. RIH WITH 1' TUBING @ 260'. COPELAND ACID MIXED & PUMPED 35 SXS CLASS A COMMON 3% CC. WAITED 2 HOURS, DID NOT TAG CEMENT. RIH W/ TUBING @ 260', COPELAND PUMPED 35 SXS CLASS A COMMON 3% CC, WAITED ON LEVEL. TAGGED @ 185'. RIH W/TUBING @ 180', COPELAND ACID MIXED & PUMPED 2% CC & 4% GEL. WAITED ON CEMENT. TAGGED CEMENT @ 130', RIH W/ TUBING @ 130', COPELAND MIXED & PUMPED 25 SXS. 60/40 POZ MIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. 125 SXS TOTAL. TICKET # 44907.

Perfs:

Top	Bot	Thru	Comments
2722	2748	OH	

Remarks: COMPLIANCE/ DENIED TA

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)

INVOICED  
JUL 12 2017

✓