

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-047-20054-00-00  
Spot: SENWSESE Sec/Twnshp/Rge: 7-25S-20W  
661 feet from S Section Line, 660 feet from E Section Line  
Lense Name: BUTLER B Well #: 1  
County: EDWARDS Total Vertical Depth: 4215 feet

Operator License No.: 30104  
Op Name: CAMBRON, PAUL L.  
Address: 118 N PENN PO BOX 384  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4215	0	WITH 100 SX CMT
SURF	8.625	268		WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/24/2017 9:00 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Revd. from: HAL HOSS Company: CHEYENNE WELL SERVICE, INC. Phone: (785) 798-5051

Proposed Plugging Method: SAND AT 4040' WITH 5 SX CMT. AT 1400' PUT 20 SX CMT. PERFORATE AT 250' & CIRCULATE CMT INSIDE & OUT

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/24/2017 5:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

BOND LOG WAS RUN. SAND PLUG PLACED & TAGGED AT 4040'. 5 SX CMT WAS PLACED ON TOP OF SAND PLUG. PERFORATE AT 250'. RUN TBG INTO 1400'. BREAK CIRCULATION WITH FRESH WATER. WELL CIRCULATED BOTH INSIDE & OUTSIDE 5 1/2" CASING. PUMP 20 SX CMT AT 1400'. PULL TBG TO 250'. BREAK CIRCULATION & PUMP 75 CMT TO FILL CASING & ANNULUS. PULL REMAINING TBG OUT OF HOLE & TOP OFF WITH CMT. HOLE STANDING FULL OF CMT

Perfs:

Top	Bot	Thru	Comments
4134	4138		

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL OILFIELD SERVICE.

Plugged through: CSG

INVOICED  
JUL 12 2017

District: 01

Signed Ken Scofield  
51A (TECHNICIAN)

RECEIVED  
JUN 13 2017  
KCC DODGE CITY