

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-099-24320-00-00
Spot: NENWSWSE Sec/Twnshp/Rge: 8-33S-18E
1300 feet from S Section Line, 2100 feet from E Section Line
Lease Name: KANSAS STATE UNIVERSITY Well #: 15-8
County: LABETTE Total Vertical Depth: 955 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	940		125 SX
SURF	8.625	20		30 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 06/13/2007 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 933' (GR-N LOG TD AT 934'), MIX UP BENTONITE & WTR, PMP SAME DWN TBG ("GEL THE WELL UP") THEN FOLLOWED W/ A 150' CMT PLUG (COVERS PERFS FROM 867' TO 797'), PU TBG TO 540', PMP IN A 140' CMT PLUG (COVERS P'FS FROM 527' TO 425') PU TBG TO 250', CIRC CMT TO SURF, POOH REST OF TBG, "TOP OFF" WELL W/ CMT, RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH", AND CLEAN UP LOC.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/13/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH 2 3/8" tbg to 907', W & W Production Co. plumped up to last jt to be run, circ and lowered same to 938' then "gelled" the well up then pmpd in a 150' cmt plug on btm, PU tbg to 540', pmpd in 140' cmt plug, PU tbg to 257', pmpd in and circ cmt to surf, PULL rest of tbg, "topped off" prod csg w/ cmt, press up on same to 300 PSI and shut well in. Will return at a later date to cut off all csg below "plow depth" and clean up loc. USED: 2 100 lb bags of bentonite, 1 sx of cotton seed hulls and 85 sx of Portland cement (20 sx btm plug, 20 sx mid plug, and 45 sx top plug)

Perfs:

Top	Bot	Thru	Comments
863	867		
805	807		
797	799		
524	527		
496	498		
490	492		
474	476		
462	465		
425	867		

RECEIVED
KCC DIST # 3
JUN 22 2017
CHANUTE, KS

RA INVOICED
JUL 12 2017

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine
(TECHNICIAN)