

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-099-24522-00-00
Spot: NESWSWSE Sec/Twnshp/Rge: 14-32S-17E
500 feet from S Section Line, 2230 feet from E Section Line
Lease Name: TREFETHEN Well #: 15-14
County: LABETTE Total Vertical Depth: 1105 feet

Operator License No.: 5150 String Size Depth (ft) Pulled (ft) Comment
Op Name: COLT ENERGY INC PROD 5.5 1090 135 SX
Address: PO BOX 388 SURF 8.625 20 5 SX
IOLA, KS 66749

Well Type: CM UIC Docket No: Date/Time to Plug: 06/13/2017 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Revd. from: REX R. ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 1087' (GR-N E-LOG TD), MIX UP BENTONITE & WTR THEN PMP SAME DWN TBG ("GEL THE WELL UP"), FOLLOWED WITH A 220' CMT PLUG (COVERS UP PERFS FROM 959 TO 892), PU TBG TO 790', PMP IN A 100' CMT PLUG (COVERS UP P'FS FROM 778' TO 732'), PU TBG TO 630' PMP IN A 100' CMT PLUG (COVERS P'FS FROM 622' TO 541'), PU TBG TO 250' CIRC CMT TO SURF THEN POOH REST OF TBG, "TOP OFF" WELL W/ CMT, RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH", AND CLEAN UP LOC.

Plugging Proposal Received By: WitnessType: NONE
Date/Time Plugging Completed: 06/13/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH 2 3/8" TBG TO 1044', HIT SOMETHING HARD, COULD NOT CIRC OR CLEAN OUT PAST SAME (44' OFF BTM OF PROD CSG, BUT 85' BELOW LOWEST PERFORATION), SO STARTED PLUG'G AT THIS DEPTH, "GELLED" UP WELL THEN PMPD IN A 557' CMT PLUG ON BTM, PU TBG TO 250', PMPD IN AND CIRC CMT TO SURFACE, POOH REST OF TBG, TOPPED OFF PROD CSG WITH CMT, PRESS UP TO 300 PSI AND SWI. WILL RETURN AT A LATER DATE, CUT OFF ALL CASING BELOW "PLOW DEPTH", AND CLEAN UP LOCATION. USED: 2 SX OF BENTONITE, 1 SX OF COTTON SEED HULLS AND 98 SX OF PORTLAND CMT (65 SX BTM PLUG AND 33 SX TOP PLUG).

Perfs:

Top	Bot	Thru	Comments
956	959		
900	902		
892	894		
776	778		
742	744		
732	738		
620	622		
604	606		
570	572		
541	959		

RECEIVED
KCC DIST # 3
JUN 22 2017
CHANUTE, KS

RH
INVOICED
JUL 12 2017

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine
(TECHNICIAN)