

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-30533-00-00  
Spot: E2W2NENW Sec/Twnshp/Rge: 22-32S-17E  
660 feet from N Section Line, 1830 feet from W Section Line  
Lease Name: WILLIS (FINK) Well #: 22-1  
County: MONTGOMERY Total Vertical Depth: 1050 feet

Operator License No.: 5150 String Size Depth (ft) Pulled (ft) Comment  
Op Name: COLT ENERGY INC PROD 4.5 1047 137 SX  
Address: PO BOX 388 SURF 8.625 21 6 SX  
IOLA, KS 66749

Well Type: CM UIC Docket No: Date/Time to Plug: 06/12/2017 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Revd. from: REX R. ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: RIH TO 1046' W/ 2 3/8" TBG, "GEL" THE WELL UP (MIXTURE OF BENTONITE & WTR), THEN PMP IN A 150' CMT PLUG AT 1046', PU TBG TO 650', PMP IN A 50' CMT PLUG, PU TBG TO 250', CIRC CMT TO SURF, POOH REST OF TBG, "TOP OFF" WELL W/ CMT, RETURN AT A LATER DATE TO CUT OFF ALL CSG, AND CLEAN UP THE LOCATION.

Plugging Proposal Received By: WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/12/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH 2 3/8" TBG TO 1044', GELLED UP THE PROD CSG THEN PMPD IN A 150' CMT PLUG ON BTM, THE TBG WAS PICKED UP TO 650' AND A 50' CMT PLUG WAS PMPD IN, PULLED UP TBG TO 251' AND CMT WAS PMPD IN AND CIRC TO THE SURFACE, REST OF THE TBG WAS PULLED OUT AND THE WELL WAS TOPPED OFF WITH CMT. PRESSURED UP TO 300+/- PSI AND SHUT THE WELL IN. WILL RETURN LATER, CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP THE LOCATION. USED: 2 100 LB SX OF BENTONITE, 1 SX OF COTTON SEED HULLS, AND 41 SX OF PORTLAND CMT (14 SX BTM PLUG, 7 SX MID PLUG, AND 20 SX TOP PLUG).

Perfs:

Top	Bot	Thru	Comments
985	988		

RECEIVED  
KCC DIST # 3  
JUN 22 2017  
CHANUTE, KS

RH

INVOICED  
JUL 12 2017

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine  
(TECHNICIAN)