

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-30587-00-00  
Spot: SEWNENE Sec/Twnshp/Rge: 21-32S-17E  
2140 feet from S Section Line, 683 feet from E Section Line  
Lease Name: FINK TRUST Well #: 21-1  
County: MONTGOMERY Total Vertical Depth: 1037 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1031		132 SX
SURF	8.625	21		6 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/13/2017 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX R. ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 1030', MIX UP BENTONITE & WTR, PMP SAME DWN TBG ("GEL THE WELL UP"), FOLLOWED W/ A 200' CMT PLUG, PU TBG TO 580', PMP IN A 50' CMT PLUG, PU TBG TO 250' THEN CIRC CMT TO SURF, POOH REST OF TBG, "TOP OFF" WELL W/ CMT, RETURN AT A LATER DATE, CUT OFF ALL CSG BELOW "PLOW DEPTH", AND CLEAN UP LOC.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: NONE  
Date/Time Plugging Completed: 06/13/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH 2 3/8" TBG TO 1029', "GELLED" THE HOLE UP THEN PMPD IN A 200' CMT PLUG ON BTM, PU TBG TO 580', PMPD IN A 50' CMT PLUG, PU TBG TO 255', PMPD IN AND CIRC CMT TO SURF, PULL REST OF TBG, "TOPPED OFF" PROD CSG W/ CMT AND PRESS UP ON SAME TO 325+/- PSI THEN SWI. WILL RETURN AT A LATER DATE TO CUT OFF ALL CSG BELOW "PLOW DEPTH" AND CLEAN UP LOC. USED: 2 100 LB BAGS OF BENTONITE, 1 SX OF COTTON SEED HULLS AND 47 SX OF PORTLAND CMT (20 SX BTM PLUG, 7 SX MID PLUG, AND 20 SX TOP PLUG).

Perfs:

Top	Bot	Thru	Comments
987	990		

RECEIVED  
KCC DIST #3  
JUN 22 2017  
CHANUTE, KS

RH

INVOICED  
JUL 12 2017

Remarks:

Plugged through: TBG

District: 03

Signed

*Russell Hine*

(TECHNICIAN)