

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-099-23952-00-00
Spot: NESESWNW Sec/Twnshp/Rge: 1-31S-17E
2150 feet from N Section Line, 1100 feet from W Section Line
Lease Name: ENEGREN Well #: 5-1A
County: LABETTE Total Vertical Depth: 1155 feet

Operator License No.: <u>5150</u>	String	Size	Depth (ft)	Pulled (ft)	Comment
Op Name: <u>COLT ENERGY INC</u>	PROD	4.5	1140		120 SX
Address: <u>PO BOX 388</u> <u>IOLA, KS 66749</u>	SURF	8.625	22		6 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 06/12/2017 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX R. ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO 1137', MIX UP BENTONITE & WTR, PUMP IN SAME THRU TBG ("GEL THE WELL UP"), FOLLOWED BY A 170' CMT PLUG (COVERS PERFS FROM 1062' TO 984', PU TBG TO 840', PMP IN A 50' CMT PLUG (COVERS P'FS FROM 826 TO 818), PU TBG TO 760', PMP IN A 150' CMT PLUG (COVERS P'FS FROM 756 TO 629), PU TBG TO 250, CIRC CMT TO SURF, POOH REST OF TBG, "TOP OFF" WELL W/ CMT, RETURN AT A LATER DATE, CUT OFF ALL CSG AND CLEAN UP LOC.

Plugging Proposal Received By: _____ Witness Type: NONE
Date/Time Plugging Completed: 06/12/2017 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

RIH 2 3/8" TBG TO 1139', "GELLED" WELL UP THEN PMPD IN A 195' CMT PLUG ON BTM, PU TBG TO 840', PMPD IN A 227' CMT PLUG, PU TBG TO 260', PMPD IN AND CIRC CMT TO SURF, PULL REST OF TBG, "TOPPED OFF" PROD CSG W/ CMT, PRESS UP TO 300 PSI, SIW. WILL RETURN AT A LATER DATE, REMOVE ALL PROD EQ AND SMOOTH OUT LOC. USED: 2 100 LB SX OF BENTONITE, 1 SX OF COTTON SEED HULLS, AND 66 SX OF PORTLAND CMT (20 SX BTM PLUG (20 SX MID PLUG, AND 26 SX TOP PLUG).

Perfs:

Top	Bot	Thru	Comments
629	1052		

RECEIVED
KCC DIST #3
JUN 22 2017
CHANUTE, KS

RH

Remarks:

Plugged through: TBG

INVOICED
JUL 12 2017

District: 03

Signed Russell Hine
(TECHNICIAN)