

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-00647-00-01
Spot: SWSSEW Sec/Twnshp/Rge: 7-20S-7W
654 feet from S Section Line, 3402 feet from E Section Line
Lease Name: MILLER OWWO Well #: 1
County: RICE Total Vertical Depth: 1254 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PLG1 | 4.5 | 1254 | | |
| PROD | 4.56 | 3560 | | 200 SX |
| SURF | 8.625 | 210 | | 175 SX |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/22/2017 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2017 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, PULL TUBING. RUN CEMENT BOND LOG INDICATING CEMENT UP TO 1020' AND AT 500' ON UP TO NEAR SURFACE. PERFOATE AT 850' RUN TUBING TO 1200' AND PUMPED 120 SX'S CEMENT WITH 100#'S COTTON HULLS, GETTING CEMENT TO SURFACE. PULLED TUBING OUT AND ATTEMPTED TOPPING OFF, STARTED GETTING WATER CIRCULATION UP BACKSIDE. SWAGED ONTO 4.5" AND PUMPED CEMENT UNTIL RAN OUT - NEVER DID GET GOOD CEMENT CIRCULATION ON BACKSIDE. CAME BACK ON 6-23-17, AND TAGGED CEMENT INSIDE 4.5" AT 275'. FILLED 4.5" AND RAN 1" DOWN BACKSIDE TO 408' AND FILLED UP BACKSIDE. PULLED 1" AND TOPPED OFF.

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1198 | 1210 | CSG | |

Remarks: DENIED TA WELL. COPELAND TICKET C-45323.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
JUL 12 2017

1/8