

TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-21692-00-00

Spot: E2NWNWSW

Sec/Twnshp/Rge: 31-33S-8W

2310 feet from S Section Line,

505 feet from W Section Line

Lease Name: DENA

Well #: 1

County: HARPER

Total Vertical Depth: 4691 feet

Operator License No.: 33936

Op Name: GRIFFIN, CHARLES N.

Address: PO BOX 347  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

PROD	5.5	4690		200 SX
------	-----	------	--	--------

SURF	8.625	265		175 SX
------	-------	-----	--	--------

TI	2.875	4505		
----	-------	------	--	--

Well Type: OG

UIC Docket No:

Date/Time to Plug: 06/22/2017 12:00 AM

Plug Co. License No.: 34082

Plug Co. Name: ALLIANCE WELL SERVICE INC.

Proposal Rcvd. from: JR GRIFFIN

Company: CHARLES GRIFFIN

Phone: (972) 342-4648

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: PARTIAL

Date/Time Plugging Completed: 06/22/2017 12:00 AM

KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

**Perfs:**

A WIRELINE CIBP WAS SET AT 4450' & CAPPED WITH 2 SKS CEMENT. THE CASING WAS PULLED AND LAYED OUT FROM 2506'. TUBING WAS RUN TO 1400', WHERE 35 SXS OF CEMENT WAS SPOTTED. TUBING PULLED TO 900' WHERE 35 SX CEMENT WAS SPOTTED. TUBING WAS PULLED TO 310' WHERE CEMENT WAS CIRCULATED TO SURFACE WITH 100 SX CEMENT.

Top	Bot	Thru	Comments
4498	4504		

Remarks: BASIC CEMENT. COMMON CEMENT

Plugged through: OK TBG

District: 02

Signed

  
(TECHNICIAN)

INVOICED  
JUL 12 2017