

5020120

P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-21,252-0000

~~S/2 SE 1/4~~, Sec. 7, T 21 S, R 8 WE

330 feet from N (S) section line

660 feet from W (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142

Lease Name Gullick Estate Well # 1

Operator: Sterling Drilling Company
Name & Address P.O. Box 129
Sterling, Kansas 67579

County Rice

Well Total Depth 3530 feet 114.73

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 212' - 225 sacks

Abandoned Oil Well X Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 10:00 AM Day: 2 Month: January Year: 1985

VERBAL PLUGGING ORDERS GIVEN TO Bob Brenneman

(company name) Kelso Casing Pulling (phone) 316 938 2457

were: Fill hole with sand to 3250 and cement with 5 sacks with
dump bailer. Squeeze hole with 5 sacks hulls, 20 sacks
Bentonite, 8 5/8" plug, and 100 sacks 50/50 Pozmix w/2% gel and
3% C.C.

Signed *Philip J. Loman*
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:45 AM Day: 2 Month: January Year: 1985

ACTUAL PLUGGING REPORT Hole Filled with sand to 3250' and cemented
with 5 sacks. Hole squeezed with 5 sacks hulls, 20 sacks
Bentonite, 8 5/8" plug, and 100 sacks 50/50 Pozmix pumped into
8 5/8" surface casing.

RECEIVED
STATE CORPORATION COMMISSION

JAN 08 1985

Remarks: 2536' of 5 1/2" casing recovered 5 1/2" - 3521-150 sacks
Wichita, Kansas Top Part 3303'
PRTD-3493' Allied Cementing Co, Inc. Ticket # 38845
Max Press. 600 PSI. Close in 300 PSI.

CONSERVATION DIVISION

Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did did not) observe this plugging.

INVOICED

DATE 1-22-85
INV. NO. 6630

Signed *Philip J. Loman*
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82