

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

STATE CORPORATION COMMISSION  
FORM CP-3  
1-8-82  
RECEIVED  
APR 14 1982  
CONSERVATION DIVISION  
Wichita, Kansas  
435  
4-14-82

API Number 15-159-21, 435

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Sterling Drilling Company

Complete Address P.O. Box 129, Sterling, Kansas 67579

Lease Name Richter Well No. 1

Location C 5/2 NE SE Sec. 7 Twp. 21 Rge. 8 (~~East~~) (West)

County Rice Total Depth 3560'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Operator and Halliburton Co.

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour: 5:30 AM Day: 5 Month: April Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

Hole circulated and Filled with mud. 50 sacks 50/50 Pozmix w/2% gel and 3% c.c. pumped through drill pipe at 300'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement through pipe.

Amount of Surface Casing: 8 5/8" - 214' - (225) Sacks 60/40 Pozmix 2% gel 3% c.c.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: \_\_\_\_\_  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Did not hear alarm. overslept

Signed: Arthur J. Loman  
Conservation Division Agent

INVOICED  
DATE 4-16-82  
INV. NO. 9957-W