

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-1-66

RECEIVED
STATE CORPORATION COMMISSION

FEB 18 1977

CONSERVATION DIVISION
Wichita, Kansas

R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 159 - 01452 - 0001 (of this well)

Operator's Full Name Lebsack Oil Production, Inc.
Complete Address Box 489, Hays, Kansas 67601
Lease Name I. Boy Well No. 2
Location C WL W/2 NE Sec. 21 Twp. 21 Rge. 10 (E) (W) X
County Rice Total Depth 2665'
Abandoned Oil Well Gas Well X Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Casing Pulling and Allied Cementing Co.
Address Box 176, Chase, Kansas License No. 683
Operation Completed: Hour 10:45 AM Day 16 Month February Year 1977

The above well was plugged as follows:

Hole filled with sand to 2500' and cemented with 5 sacks cement.

Hole squeezed with 25 sacks gel-mud, 6 sacks hulls, 75 sacks cement,
7 sacks gel-mud, 5 sacks hulls, and 25 sacks cement pumped into 13-3/8"
surface casing that had been orange-peeled back to an 8-5/8" collar.

2201' of 5 1/2" casing recovered.

I hereby certify that the above well was plugged as herein stated.

Signed: *William J. Loman*

Well Plugging Supervisor

INVOICED

DATE 2-18-77

INV. NO. 4658-W