

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-23920-00-02
Spot: NWSWSE Sec/Twnshp/Rge: 28-25S-15E
828 feet from S Section Line, 2176 feet from E Section Line
Lease Name: HARTZLER Well #: 29
County: WOODSON Total Vertical Depth: 1205 feet

Operator License No.: 33900
Op Name: LEIS, STEVEN A.
Address: 1135 30TH RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1205		135 sx
SURF	7	40		10 sx

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 05/16/2017 12:00 AM

Plug Co. License No.: 33900 Plug Co. Name: LEIS, STEVEN A.

Proposal Rcvd. from: STEVE LEIS Company: _____ Phone: _____

Proposed Plugging Method: Staging plugs Set a 50ft plug at the bottom Set a 50ft plug at the BKCFill the casing from 250ft to surface

Plugging Proposal Received By: _____

Witness Type: NONE

Date/Time Plugging Completed: 05/16/2017 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the inside of the 2.875" casing which was cemented inside the 7" surface casing to TD. Pumped and placed 70' cement plug at TD. Pulled 1" pipe up to 775'. Pumped and placed 50' cement plug at 775'. Pulled 1" pipe up to 250'. Pumped and circulated cement from 250' to surface. Pulled the rest of the 1" pipe and topped the well off with cement. A total of 12 sacks of portland cement was reported used to plug this well.

Top	Bot	Thru	Comments
1168	1176		

RECEIVED
KCC DIST #3
JUN 26 2017
CHANUTE, KS

RD

Remarks:

Plugged through: TBG

District: 03

Signed [Signature] E.C.R.S.
(TECHNICIAN)

INVOICED ^{Form CP-2/3}
JUL 12 2017