

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-23852-00-00
Spot: NWNESWSE Sec/Twnship/Rge: 28-25S-15E
1006 feet from S Section Line, 1937 feet from E Section Line
Lease Name: HARTZLER Well #: 17
County: WOODSON Total Vertical Depth: 1200 feet

Operator License No.: 33900

Op Name: LEIS, STEVEN A.

Address: 1135 30TH RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1200		110 SX
SURF	7	40		10 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/16/2017 12:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: STEVE LEIS

Company:

Phone: (620) 330-6328

Proposed Plugging Method: Stage Plugs 50' Plug at TD 50' Plug at the BKCFill casing from 250' to surface

Plugging Proposal Received By:

Witness Type: NONE

Date/Time Plugging Completed: 05/16/2017 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the inside of the 2.875" casing which was cemented inside the 7" surface casing to TD. Pumped and placed 70' cement plug at TD. Pulled 1" pipe up to 775'. Pumped and placed 50' cement plug at 775'. Pulled 1" pipe up to 250'. Pumped and circulated cement from 250' to surface. Pulled the rest of the 1" pipe and topped the well off with cement. A total of 12 sacks of portland cement was reported used to plug this well.

RECEIVED
KCC DIST # 3
JUN 26 2017
CHANUTE, KS

RD

INVOICED

JUL 12 2017

Remarks:

Plugged through: TBG

District: 03

Signed


E. C. A. S.
(TECHNICIAN)