

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-21499-00-00
Spot: SESESW Sec/Twnshp/Rge: 15-30S-7W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: PULLIAM -(TENNECO) Well #: 1-15
County: KINGMAN Total Vertical Depth: 4275 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S MAIN ST
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4273		125 SX
SURF	8.625	259		175 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 06/22/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 532-5400

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 06/22/2017 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

30 SX OF CEMENT & 50# OF HULLS WAS PUMPED DOWN 5 1/2" TO 3800' TO CLOSE PERFS. SHUT IN PRESSURE WAS 1000 PSI. RECOVERED CASING FROM 3060' AND PULLED TO 1200' WHERE WE PUMPED 12 BAGS OF GEL AND 50 SX CEMENT. LET SET 1 1/2 HOURS AND TAGGED CEMENT AT 975'. PULLED CASING TO 900' AND SPOTTED 35 SX CEMENT. PULLED CASING TO 300' AND CIRCUALTED CEMENT TO 0' WITH 100 SKS CEMENT.

Top	Bot	Thru	Comments
4184	4194		

INVOICED

INVOICED

JUL 13 2017

Remarks: QUALITY WELL SERVICE COMMON CEMENT

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)