

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-20615-00-02  
Spot: NESENW Sec/Twnshp/Rge: 15-30S-7W  
3630 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: PULLIAM -(TENNECO) Well #: 2-15  
County: KINGMAN Total Vertical Depth: 4526 feet

Operator License No.: 4706  
Op Name: MESSENGER PETROLEUM, INC.  
Address: 525 S MAIN ST  
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	4504		800 SX
SURF	9.625	382		300 SX

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2017 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: (620) 532-5400

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/29/2017 5:00 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

**Perfs:**

PUMPED 50 SX CEMENT AND 100# HULLS TO 3800'. GAS CHANNELED THRU CEMENT. CAPPED CEMENT WITH 100' AND SAND AND 7 SKS CEMENT. CEMENT BOND LOG SHOWED CEMENT TO 1000' AND BACKSIDE OF 7" CASING. RECOVERED CASING FROM 850' AND PULLED 50 700'. SPOTTED 50 SX. PULLED CASING TO 300' AND CIRCUALTED CEMENT TO SURFACE WITH 150 SX CEMENT.

Top	Bot	Thru	Comments
4094	4104		

INVOICED  
JUL 13 2017

Remarks: QUALITY WELL SERVICE CLASS A CEMENT

Plugged through: CSG

District: 02

Signed   
(TECHNICIAN)