

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-21791-01-00  
Spot: S2S2SESE Sec/Twnshp/Rge: 14-35S-7W  
200 feet from S Section Line, 660 feet from E Section Line  
Lease Name: HOPKINS Well #: 1-14H  
County: HARPER Total Vertical Depth: 4941 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		9 sx cement
	11 7	5385		485 sx cement
	L1 4.5	9560		730 sx cement
PROD	9.62	2506		275 SX
SURF	13.37	610		720 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/15/2017 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (405) 429-6002

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/18/2017 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4900' ON TUBING. BP RELEASED FROM TUBING HOLE LOADED WITH MUD & 100 SX CEMENT. RECOVERED CASING FROM 2561' & LAYED OUT. TIH WITH TUBING TO 1150' SPOT 75 SX CEMENT. LAY TUBING OUT TO 650' & SPOT 100 SX CEMENT. LAY TUBING OUT TO 300' & CIRCULATE CEMENT TO SURFACE WITH 95 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
8187	8693		
7558	8064		
6928	7434		
6299	6805		
5669	6175		
5070	5546		

INVOICED

JUL 13 2017

Remarks: ORR ENTERPRISES, CLASS C CEMENT. TMD = 12.642

Plugged through: TBG

District: 02

Signed [Signature] DISTRICT SUPERVISOR  
(TECHNICIAN)