

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21790-01-00
Spot: N2N2NWNW Sec/Twnshp/Rge: 5-33S-6W
200 feet from N Section Line, 660 feet from W Section Line
Lease Name: FERRIS Well #: 1-5H
County: HARPER Total Vertical Depth: 4546 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	53		10 sx cement
	11	7	4929	200 sx cement
PROD	4.5	9999		630 sx cement
SURF	9.63	670		430 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2017 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 06/13/2017 7:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

TIH WITH CIBP ON TUBING. SET CIBP AT 4482'. RELEASE TUBING & CIRCULATED HOLE WITH MUD. SPOT 50 SKS ON CEMENT ON BP. TOH WITH TUBING. RECOVER CASING FROM 1326'. TIH WITH TUBING TO 1300' AND SPOT 50 SKS CEMENT. PULL TUBING TO 720' SPOT 50 SXS CEMENT. PULL TUBING TO 300' AND CIRCULATE CEMENT TO SURFACE WITH 100 SKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
8519	8898		
8046	8246		
7574	7954		
7102	7481		
6629	7009		
6157	6537		
5685	6064		
5212	5592		
4740	5120		

Remarks: ORR ENTERPRISES. CLASS C CEMENT. TMD = 11,305

Plugged through: TBG

District: 02

Signed Judd Klok, District Supervisor
(TECHNICIAN)

INVOICED

JUL 13 2017