

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21754-01-00

Spot: SWSWSESW

Sec/Twnshp/Rge: 14-35S-6W

200 feet from S Section Line,

1450 feet from W Section Line

Lease Name: CYNTHIA

Well #: 1-14H

County: HARPER

Total Vertical Depth: 5238 feet

Operator License No.: 34192

Op Name: SANDRIDGE EXPLORATION AND PRO

Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		18 SX
L1	4.5	9306		450 SX
PROD	7	5238		245 SX
SURF	9.63	713		350 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/18/2017 12:00 AM

Plug Co. License No.: 33338

Plug Co. Name: ORR ENTERPRISES, INC.

Proposal Rcvd. from: RONNIE ORR

Company: ORR ENTERPRISES

Phone: (405) 429-6002

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: PARTIAL

Date/Time Plugging Completed: 05/22/2017 12:00 AM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

TIH WITH 7" CIBP ON TUBING. SET CIBP @ 3740'. RELEASED PLUG & CIRCUALTED MUD TO SURFACE, SPOTTED 50 SX CEMENT. CUT & PULLED 7" CASING FROM 1138'. TIH WITH TUBING TO 1100' & SPOTTED 50 SX CEMENT. PULLED TUBING TO 760' & SPOTTED 50 SX CEMENT. PULLED TUBING TO 300' & CIRCUALTED CEMENT TO SURFACE WITH 100 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
8908	8911		
8763	8766		
8618	8621		
8473	8476		
8329	8332		
8184	8187		
8039	8042		
7894	7897		
7750	7753		
7605	7608		
7460	7463		
7316	7319		
7171	7174		
7026	7029		
6881	6884		
6737	6740		
6592	6595		
6447	6450		
6303	6306		
6158	6161		
6013	6016		
5868	5870		
5724	5727		
5579	5582		
5434	5437		
5289	5292		
5145	5148		
5000	5003		

INVOICED

JUL 13 2017

Remarks: ORR ENTERPRISES CLASS C CEMENT. TMD = 9308

✱