

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-20893-00-00
Spot: W2NW Sec/Twnshp/Rge: 21-33S-6W
1320 feet from N Section Line, 660 feet from W Section Line
Lease Name: BASSFORD Well #: 1
County: HARPER Total Vertical Depth: 4535 feet

Operator License No.: <u>34192</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>SANDRIDGE EXPLORATION AND PRO</u>	PROD	4.5	4508		500 SX
Address: <u>123 ROBERT S. KERR AVE</u>	PROD	4.5	4532	1212	
<u>OKLAHOMA CITY, OK 73102</u>	SURF	8.625	255		170 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/19/2017 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 06/20/2017 5:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

TIH WITH CIBP ON TUBING. SET CIBP AT 4386'. RELEASED BP FROM TUBING AND PUMPED 70 BBLs OF MUD IN CASING. PUMPED 20 SKS CEMENT ON BP. TOH WITH TUBING. RECOVER & LAYED DOWN 1212' OF 4 1/2" CASING. TIH WITH TUBING TO 1200', SPOT 50 SX CEMENT. PULL TUBING TO 750', SPOT 50 SX CEMENT. PULL TUBING TO 300' AND CIRCULATED CEMENT TO SURFACE WITH 100 SX CEMENT.


Perfs:

Remarks: ORR ENTERPRISES CLASS C CEMENT

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

INVOICED
JUL 13 2017

/*