

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-077-21890-01-00
Spot: N2S2NWNE Sec/Twnshp/Rge: 5-33S-6W
800 feet from N Section Line, 1980 feet from E Section Line
Lease Name: CONNIE 3206 Well #: 2-32H
County: HARPER Total Vertical Depth: 5085 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	100		10 sx cement
	11 7	5085		300 sx cement
	L1 4.5	8114		400 sx cement
PROD	4.5	8114		400 SX
SURF	9.63	697		380 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2017 12:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 05/25/2017 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

TIH WITH 7" CIBP ON TUBING AND SET AT 4463'. RELEASE BP AND CIRCULATE MUD TO SURFACE. SPOT 50 SKS CEMENT ON BP AND TOH WITH TUBING. RECOVERED AND LAYED OUT. 1108' OF 7" CASING. TIH WITH TUBING TO 1100' AND SPOT 50 SX CEMENT. PULL TUBING TO 750' & SPOT 50 SX CEMENT. PULL TUBING TO 300' & CIRCULATED CEMENT TO SURFACE WITH 100 SKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
7572	7929		
7016	7495		
6477	6909		
6030	6384		
5580	5955		
5090	5476		

INVOICED
JUL 18 2017

Remarks: ORR ENTERPRISES CLASS C CEMENT TMD = 8114

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)