

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-155-21676-01-00  
Spot: NWNEENE Sec/Twnshp/Rge: 30-24S-10W  
175 feet from N Section Line, 600 feet from E Section Line  
Lease Name: BLACK FARMS 30 Well #: 1-H  
County: RENO Total Vertical Depth: 4058 feet

Operator License No.: 33596  
Op Name: UNIT PETROLEUM COMPANY  
Address: 8200 SOUTH UNIT DRIVE  
TULSA, OK 74132

String	Size	Depth (ft)	Pulled (ft)	Comments
I1	9.625	1530		580 SX
I2	7	4058		160 SX
PROD	7	4058		160 SX
PROD	5.5	8440		510 SX
SURF	16	140		144 SX
SURF	9.625	1530		580 SX
T1	2.825	3810		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/10/2017 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: BRENT KEYS Company: ORR ENTERPRISES Phone: (918) 477-4510

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/12/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET 4 1/2" CIBP @ 4013'. CIRCULATE HOLE W/90 BBLs MUD & CAP PLUG W/ 50 SKS CLASS "C" CEMENT @ 4013'-3519'. CUT 5 1/2" CSG @ 1620'. UNABLE TO PULL 5 1/2" CASING. OK'D TO PERF & SQUEEZE BY BJ HOPE W/ KCC. PERF 5 1/2" CASING @ 1580'. TIH W/TUBING @ 1580' & SPOT 100 SKS CEMENT. POH W/TUBING & LOAD CASING & SQUEEZE 10 BBLs CEMENT INTO PERFS @ 1580'-1160'. WOC. TIH W/TBG & TAG TOC @ 1305'. PERF 5 1/2" CASING @ 900'. TIE ONTO 5 1/2" CASING & ESTABLISH CIRCULATION BETWEEN CASING STRINGS & SQUEEZE W/50 SKS CEMENT @ 900'-700'. WOC. PERF 5 1/2" CASING @ 250'. TIE ONTO 5 1/2" CASING & ESTABLISH CIRCULATION TO SURFACE ON 5 1/2" X 7" ANNULUS & ON 7" X 9 5/8" ANNULUS. CIRCULATE TO SURFACE W/70 SKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4200	8225		

INVOICED  
JUL 13 2017

Remarks: TMD = 8440

Plugged through: TBG

District: 02

Signed B. J. Hope  
(TECHNICIAN)