

TO: ..  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20510-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 35-21S-41W  
1250 feet from S Section Line, 1250 feet from E Section Line  
Lease/Unit Name: STAATS Well Number: 2-35  
County: HAMILTON Total Vertical Depth: 2795 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

Conductor Pipe: Size feet: 890.84  
Surface Casing: Size 8.625 feet: 323 WITH 200 SX CMT  
Production: Size 4.5 feet: 2794 WITH 700 SX CMT  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/21/2002 10:15 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP DOWN 4 1/2" 400# HULLS & 135 SX CMT. PRESSURE TEST. PUMP DOWN ANNULUS 20 SX CMT. PRESSURE TEST.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/21/2002 11:00 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2785'. PERFS AT 2752-56 & 2760-66'. PUMPED DOWN 4 1/2" CASING 400# HULLS & 135 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN AT 800#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 20 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 500#.

RECEIVED

MAR 29 2002

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin D. Strube  
(TECHNICIAN)

INVOICED

MAR 26 2002

DATE March 29-02

INV. NO. 2002061583

Form 01/2/3