

STATE OF KANSAS
STATE CORPORATION COMMISSION


Steeling Drilling
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rice County. Sec. 20 Twp. 21 Rge. 10 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
440' FEL 440' FNL

Lease Owner Lebsack Oil Production, Inc.
Lease Name Taylor #1 Well No.

Office Address Hays, Kansas 67601
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/7/79 19
Plugging completed 9/11/79 19
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Toman
Producing formation Depth to top Bottom Total Depth of Well 3430
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8 | 204 | none |
| | | | | 4 1/2" | 3427 | 1815' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded to 3400' and ran 3 sacks cement. Loaded hole, shot pipe at 2008', 1817',
worked pipe loose and pulled 57 joints. Pumped 3 sacks hulls, 20 sacks gel and
85 sacks 50-50 pos, 2% gel.

PLUGGING COMPLETE.:

9-20-79

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1979
CONS. DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) *R. Darrell Kelso*
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of Sept., 1979

Margaret Melcher
Notary Public.

My commission expires _____



STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG ----- TAYLOR #1
440' FEL, 440' FNL, Section 20-21S-10W, Rice County,
Kansas

OWNER: Taylor Equipment Company and Lebsack Oil Company, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 29, 1975
COMPLETED: January 5, 1976

TOTAL DEPTH: 3430'

LOG

CASING RECORD

0 - 670 Sand and Shale

670 - 3430 Lime and Shale

Ran 5 joints of 8 5/8", 28# used casing, 202.62'
pipe set at 214' K.B. Cemented with 200 sacks
60/40 Pozmix with 3% cc. Plug down at 6:15 PM,
12-29-75.

Ran 109 joints 4 1/2" OD, 10.5# casing, 3427.12'
cemented at 3427' K.B. with 150 sacks Howco
light, followed with 100 sacks Pozmix with
18% salt. Plug down at 8:35 PM, 1-5-76.

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1979

REGISTRATION DIVISION
Wichita, Kansas