


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 North Broadway  
Wichita, Kansas

McPherson County, Sec. 13 Twp. 21S Rge. 3 (X) (W)  
Location as "NE/CNW/SW" or footage from lines NW NW SW  
Lease Owner Anschutz Drilling Co., Inc.,  
Lease Name Flickner Well No. 1  
Office Address 709 Union National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 23 19 56  
Application for plugging filed August 23 19 56  
Application for plugging approved August 23 19 56  
Plugging commenced August 23 19 56  
Plugging completed August 23 19 56  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee  
Producing formation Depth to top Bottom Total Depth of Well 3752 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	205	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy rotary mud to 200 ft. Wood rock and hull bridge at 250 ft. with 15 sacks cement on bridge. Hole filled with heavy rotary mud to 20 ft. Wood rock and hull bridge at 20 ft. Cap plug with 5 sacks cement.

9-7-56

(IF additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor White & Ellis Drilling, Inc., License #209  
Address Box 448 El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
Bruce Auer, employe of contractor (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bruce Auer  
El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of August, 19 56

My Commission Expires April 14, 1958

Dale R. Daniel Notary Public.

PLUGGING  
FILE SEC 13 T 21 R 3W  
BOOK PAGE 93 LINE 39

Casing Record:

8-5/8" O 205' with 75 sacks cement

T.D. 3752

Kelly bushing measurements 5' above ground level

Location:

NW NW SW Sec. 13-21S-3W

McPherson County, Kansas

Farm:

Flickner #1

Well Owner:

Anschutz Drilling Co., Inc.

Contractor:

White & Ellis Drilling, Inc.

Started:

August 8, 1956

Completed:

August 23, 1956

Formation                      Depth - Figures indicate bottom of formation

Soil	0 - 2	Top of Kinderhook
Clay	38	
Sod	112	Shale 3621
Sand	132	
Shale & lime streaks	200	Top of Viola
Lime	204	
Lime & shale streaks	240	Lime 3649
Shale	530	
Lime	585	Top of Simpson
Shale & shells	760	
Shale & lime streaks	850	Dolomite & sand 3727
Lime	920	
Shale	1025	Top of Arbuckle
Lime	1140	
Shale & lime streaks	1260	Lime 3752
Lime & shale	1300	
Shale & shells	1375	
Shale & lime streaks	1450	Dry hole, plugged and abandoned.
Shale & shells	1490	
Shale & lime streaks	1535	
Shale & shells	1595	
Shale & lime	1745	
Lime	1820	
Shale & lime streaks	1900	
Lime	1940	
Lime & shale	1965	
Lime	2010	
Lime & shale	2065	
Lime	2206	
Shale & sandy shale	2265	
Shale & shells	2365	
Shale & lime streaks	2433	

Top of Lansing

Lime 2615

Top of Kansas City

Lime	2775
Sandy lime	2785
Lime	2810
Lime & shale	3023
Shale & lime streaks	3105
Shale	3134

Top of Mississippi

Lime 3378

**PLUGGING**  
 FILE SEC. 13 T. 21 R. 3W  
 BOOK PAGE 43 LINE 39