

5 030534

11-13

15.113.20240.0001

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C W/2 SE SE, SEC. 34, T. 21 S, R. 3 W/EX  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 113-20,240A  
660 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568  
Operator: Kaiser-Francis Oil Company  
Name & Address: P. O. Box 21468  
Tulsa, OK 74121-1468

Lease Name Goering Well # 1  
County McPherson 116.68  
Well Total Depth 3590 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8-5/8 feet 160

Abandoned Oil Well Gas Well  Input Well SWD Well D&A  
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address

Company to plug at: Hour: am Day: 8 Month: 11 Year: 19 89

Plugging proposal received from Darrell Kelso  
(company name) Kelso Casing Pulling (phone) 316-938-

were: 4-1/2 @ 3292' w/225 sx - plugged back w/sand to 3100' - cap with 4 sx -  
shoot pipe 2000' - recover pipe - pump down 4-1/2 casing - circ cmt to surface  
from 450'

Plugging Proposal Received by Merlan Unruh  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part top None

Operations Completed: Hour: 16:30 Day: 8/13 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT Bailer lost in hole w/sand line approx 1200' - pumped  
12 bbls fluid - pressured up 1000# - held - no drop in PSI - hooked up to surface  
casing pumping @ 200# - mixed 2 sx gel followed with approx 120 sx w/1/2 sx  
hulls - max 250# - shut in 200# - ran 1" tubing in 4-1/2" casing to 500' H.Circ.  
cement to surface.

11/8/89 - B. J. Titan #545043 11/13/89 - B.J. Titan #545046 DEC 6 1989

Remarks: (If additional description is necessary, use BACK of this form. Wichita, Kansas

did observe this plugging.

INVOICED

Signed Merlan Unruh  
(TECHNICIAN)

DATE DEC 08 1989

WIK. NO. 26716

11-13