

10-22

RECEIVED
KANSAS CORPORATION COMMISSION

2-

NOV 03 1993

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-113-21,048-0000
N/2 SW NW, SECTION 34 TOWNSHIP 21 RANGE 3W

OPERATOR LICENSE # 5350 3630 FEET FROM S SECTION LINE
4720 FEET FROM E SECTION LINE

OPERATOR BRUNSON PRODUCTION, INC.
NAME & 125 N. EMPORIA STE 200
ADDRESS WICHITA, KS 67202

LEASE NAME: L NEUFELDT #1

COUNTY: MCPHERSON 113.75
WELL TOTAL DEPTH: 3500' (3300')

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 220'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: BRUNSON PRODUCTION INC
ADDRESS: _____ LICENSE: 5350

COMPANY TO PLUG AT: HOUR: 1430 DAY: 22 MONTH: 10 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: DALE P JEWETT
COMPANY NAME: BRUNSON PRODUCTION INC PHONE: 316-662-5207

WERE: SAND TO 3075' AND TOP W/5 SX CMT - CUT PIPE OFF AND
PULL TO 575' - SPOT 35 SX CMT @ 575' - PULL PIPE TO
325' & CIRC CMT TO SURF
PERFS @ 3466-67' & 3132-58'
5-1/2" CSG @ 3499'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 16:30 DAY: 22 MONTH: 10 YEAR: 1993

ACTUAL PLUGGING REPORT:
SANDED TO 3070' & TOPPED W/5 SX CMT - CUT PIPE OFF @
2243' - PULLED PIPE TO 575' & SPOTTED 35 SX CMT -
PULLED PIPE TO 325' & CIRC 190 SX CMT TO SURF -
RETRIEVED 2243' OF 5-1/2" CSG

REMARKS: USED 60/40 POZ W/4% GEL BY UNITED #4513

INVOICED

I DID OBSERVE THIS PLUGGING.

DATE 11-8-93

/s/ _____
Michael R. Wilson (AGENT)

INV. NO. 39162

FORM CP-2/3
REV. 3/90

10-22



Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

February 22, 1983

COMPANY: BRUNSON PRODUCTION INC.
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: NEUVELDT #1
 LOCATION: 330' FNL & 560' FWL S/2 NW/4 Section 34-21-3W
 McPherson County, Kansas
 COMMENCED: February 15, 1983
 COMPLETED: February 22, 1983
 ELEVATION:

0	to	20	Clay
20	to	170	Sand & Shells
170	to	610	Shale
610	to	945	Shale & Lime
945	to	1290	Lime & Shale
1290	to	1750	Shale & Lime
1750	to	1945	Lime & Shale
1945	to	2745	Shale & Lime
2745	to	2935	Lime
2935	to	3070	Lime & Shale
3070	to	3128	Shale & Lime
3128	to	3344	Mississippi
3344	to	3355	Mississippi Lime
3355	to	3445	Kinderhook
3445	to	3461	Shale & Lime
3461	to	3500	Hunton
		3500	T. D.

Cut 12 1/2" hole to 220' and run 222' of 8 5/8" surface casing, cemented with 150 sacks of cement at 220'. Plug down at 1:00 P. M., February 15, 1983. Run 3502.50' of 5 1/2" casing, cemented with 125 sacks of cement at 3499', 1 foot off bottom at 3499'. Plug down at 7:00 A. M., February 22, 1983.

TOPS: MISSISSIPPI - 3128' KINDERHOOK - 3355' HUNTON - 3461'

Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true & correct copy of your log on the Naufaldt #1, located on the 330' FNL & 560' FWL S/2 NW/4 Section 34-21-3W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.

P. E. Plouffe
 P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 22nd day of February, 1983.

Johnnie L. Schmidt
 Johnnie L. Schmidt - Notary Public

JOHANNIE L. SCHMIDT
 McPherson County, Kansas
 My Appl. Exp. June 22, 1983

RECEIVED
 STATE CORPORATION COMMISSION

OCT 08 1993