

1 040998.

9-6

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 075-20,567-0000  
NE NE SW, SEC. 13, T 21 S, R 39 W/E  
2310 feet from S section line  
2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Lease Name Danial Morgan Well # I-13

Operator: Amoco Production Co.

County Hamilton 175.163

Name & Address P.O. Box 800, Room 924

Well Total Depth 5404 feet

Denver, CO 80201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 392

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Cheyenne Drilling License Number 316-277-2062

Address P.O. Box 916, Garden City, KS 67846-0916

Company to plug at: Hour: 8 p.m. Day: 6 Month: 9 Year: 19 95

Plugging proposal received from Sam Carmack

(company name) Amoco Production Co. (phone) 316-356-6936

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2323'

1st plug at 2325' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,

3rd plug at 600' with 30 sx cement, 4th plug at 420' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:30 p.m. Day: 6 Month: 9 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 2325' with 50 sx cement,

2nd plug at 1200' with 80 sx cement, 3rd plug at 600' with 30 sx cement,

4th plug at 420' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.

(if additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 9-21-95  
INV. NO. 43554

Signed Stephen J. Pfeifer (TECHNICIAN)

EFFECTIVE DATE: 8-15-95  
 DISTRICT # 1  
 STATE Wyo

State of Wyoming  
 NOTICE OF INTENTION TO DRILL 15 075-20,567-0000

FORM MUST BE FILLED  
 ALL BLANKS MUST BE FILLED

Must be approved by the R.C.C. five (5) days prior to commencing well

Expected Spud Date August 11, 1995  
 month day year

NE NE SW sec 13 Twp 21S S, Rg 39 East  
 West

OPERATOR: License # 5952  
 Name: Amoco Production Company  
 Address: P.O. Box 800, Room 924  
 City/State/Zip: Denver, Co. 80201  
 Contact Person: Susan R. Potts  
 Phone: 303-830-5323

2310 feet from Source / North line of Section  
 2310 feet from East / East line of Section  
 IS SECTION X REGULAR        IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)  
 County: Hamilton  
 Lease Name: Daniel Morgan Well #: 1-13  
 Field Name: Wildcat

CONTRACTOR: License # 5382  
 Name: Cheyenne Drilling

\* Is this a Prorated/Spaced Field?        yes X.. no  
 Target Formation(s):        Morrow  
 Nearest lease or unit boundary:        2310  
 Ground Surface Elevations:        3406.39 feet XSL  
 Water well within one-quarter mile:        yes X.. no  
 Public water supply well within one mile:        yes X.. no  
 Depth to bottom of fresh water:        200  
 Depth to bottom of usable water:        1150  
 Surface Pipe by Alternate:        1 X.. 2  
 Length of Surface Pipe Planned to be set:        220  
 Length of Conductor pipe required:         
 Projected Total Depth:         
 Formation at Total Depth:         
 Water Source for Drilling Operations:  
 .. well .. farm pond X.. other  
 O&G Permit #:         
 Will Core be Taken?        yes .. X.. no  
 If yes, proposed zone:       

Well Drilled For: Well Class: Type Equipment:  
 ... Oil ... Enh Acc ... Infield X.. Rod Rotary  
X Gas ... Storage ... Pool Ext. ... Air Rotary  
 ... O&G ... Disposal X.. Wildcat ... Cable  
 ... Seismic; ... # of Holes ... Other  
 ... Other  
 If O&G: old well information as follows:  
 Operator:         
 Well Name:         
 Comp. Date:        Old Total Depth       

Directional, Deviated or Horizontal wellbore?        yes X.. no  
 If yes, true vertical depth:         
 Bottom Hole Location:       

Exp. 2/10/96

AFFIDAVIT

RECEIVED  
 WYOMING OPERATIONS COMMISSION

\* PRORATED IN CHASE

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with W.S. 1-101, et. seq.  
 SEP 10 1995

Pusher Susan  
 SPUD DATE 8-28-95 INITIALS IPR  
 LENGTH SURFACE PLANNED 400 +  
 RESERVE PIT STATUS- REMOVE FLUID LINED  
 after salt sect.        bbls.        when done        bbls.  
 RATHOLED AHEAD? Y N SIZE HOLE  
 SURFACE PIPE 2 3/8 @ 392 CONDUCTOR  
 ANHYDRITE T- B-2323 ELEVATION  
 TD 5404 FORMATION St. Louis  
 RAN PIPE @        DV TOOL        ALT II DONE  
 @        SX        Y        N  
 Arbuckle Plug @        Ft. W/        SX  
       Hug./Council @ 3380 Ft. W/ 8 SX  
       Anhydrite Base @ 2325 Ft. W/ 50 SX  
       1/2 Base Anhy. @ 1200 Ft. W/ 80 SX  
       1/2, 1/2 Plug @ 600 Ft. W/ 30 SX  
       Bottom Surface @ 420 Ft. W/ 50 SX  
       40' Plug @ 40 Ft. W/ 10 SX  
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX  
 WATER WELL        SX (Irr. Well        Pond       )  
       Hauling         
 TECHNICIAN S.P. DATE 9-6-95  
 TYPE OF CEMENT 60/40 per 6" @ 14" flow-line  
 STARTING TIME        (AM/PM) DATE 9-6-95  
 COMPLETION TIME 13:30 (AM/PM) DATE 9-6-95  
 CEMENT COMPANY Acad