

To: 1 060192
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-11

API NUMBER 15- 093-21,247-0000
SE NW NE , SEC. 22 , T 21 S, R 38 W/X
4290 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5939
Operator: Vess Oil Corporation
Name & Address: 8100 E. 22nd St. N, Bldg. 300
Wichita, KS 67226

Lease Name Maune Well # 1-22
County Kearny 159.25
Well Total Depth 4900 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 475

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 30606
Address E. Highway 24, Box 130, Hill City, KS

Company to plug at: Hour: 1:30 p.m. Day: 11 Month: 10 Year: 1993
Mike Stanton

Plugging proposal received from _____
(company name) Murfin Drilling Co. (phone) 913-674-2103

were: 4 1/2" at 4134' w/770 sx cement, PBSD 4073', Perfs at 4029-35'.

- 1st plug set CIBP at 3980' and dump 2 sx cement on top,
- 2nd plug at 1200' with 50 sx cement,
- 3rd plug at 750' with 50 sx cement,
- 4th plug at 500' with 40 sx cement. 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4:30 p.m. Day: 11 Month: 10 Year: 1993


ACTUAL PLUGGING REPORT 1st plug set CIBP at 3979' with 2 sx cement on top,
2nd plug at 1200' with 50 sx cement,
3rd plug at 850' with 50 sx cement,
4th plug at 500' with 50 sx cement,
5th plug at 40' with 10 sx cement,

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1728' of 4 1/2" casing.
If additional description is necessary, use BACK of this report.

DATE (of next observation) observe this plugging.

INV. NO. 39096 3 1993

Signed Car (TECHNICIAN)



INVOICED