

1070090

TO: STATE CORPORATION COMMISSION 1-11

API NUMBER 15-075-20,693-0000
NW SW SW SEC. 14, T 21 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME, BURNETT WELL # 13-14

TECHNICIAN'S PLUGGING REPORT COUNTY HAMILTON

OPERATOR LICENSE # 32059 WELL TOTAL DEPTH 5410 195.83 FEET

OPERATOR: GULF PRODUCTION CORP. PRODUCTION CSG: SIZE @ ' WITH SX

NAME AND 9701 N BROADWAY SURFACE CASING: SIZE 8 5/8" @ 362' WITH SX

ADDRESS OKLAHOMA CITY, OK 73114

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MURFIN DRILLING LICENSE NUMBER 30606

ADDRESS 250 N WATER, SUITE 300, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 9:05 PM DAY: 11 MONTH: 01 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM GUS

(COMPANY NAME) MURFIN DRILLING (PHONE) 316-267-3241

WERE:

1ST PLUG AT 2097' WITH 50 SX CEMENT. 2ND PLUG AT 1221' WITH 80 SX CEMENT.

3RD PLUG AT 390' WITH 40 SX CEMENT. 4TH PLUG AT 0-40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 11:18 PM DAY: 11 MONTH: 01 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2097' WITH 50 SX CEMENT. 2ND PLUG AT 1221' WITH 80 SX CEMENT.

3RD PLUG AT 390' WITH 40 SX CEMENT, 4TH PLUG AT 0-40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1999

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY HALLIBURTON CONSERVATION DIVISION

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING.

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3

1-22-99
60560 1-11