

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-10070-00-00  
Spot: CSENV Sec/Twnshp/Rge: 25-21S-41W  
1980 feet from N Section Line, 1980 feet from W Section Line  
Lease/Unit Name: HCU Well Number: 2511  
County: HAMILTON Total Vertical Depth: 2791 feet

Operator License No.: 32971 Conductor Pipe: Size \_\_\_\_\_ feet: 890.71  
Op Name: DOMINION OKLAHOMA TEXAS EXPL & Surface Casing: Size 8.625 feet: 196 WITH 165 SX CMT  
Address: 14000 QUAIL SPRINGS PKWY, # 600 Production: Size 4.5 feet: 2791 WITH 100 SX CMT  
OKLAHOMA CITY, OK 73134 Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/12/2002 3:00 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: BOTTOM PLUG THROUGH TUBING 100# HULLS & 20 SX CMT. PTOH. SHOOT CASING AND PULL OUT OF HOLE. RTIH TO 1200' & PUMP 40 SX CMT. 40 SX CMT AT 600'. 40 SX CMT AT 230'. 10 SX CMT AT 40'.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/14/2002 12:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:  
PBT 2788'. PERFS AT 2776, 2782-85'. ON 03/12/02: PUMP DOWN 2 7/8" TUBING 100# HULLS & 20 SX CMT. MAXIMUM PRESSURE 1000#. ON 03/13/02: PACKER ON 2 7/8" AT 2734'. PULLED 2 7/8" OUT OF HOLE. PRESSURE TESTED 4 1/2" CASING 1200' TO 0', CIRCULATED UP 8 5/8" X 4 1/2" ANNULUS. 1ST PLUG SHOT 4 1/2" CASING AT 1200'. RAN 1 1/4" TUBING TO 1230' & PUMPED 40 SX CMT. PULLED TUBING OUT OF HOLE. 2ND PLUG SHOT 4 1/2" AT 614', PULLED CASING OUT. 03/14/02: 3RD PLUG RAN TUBING IN HOLE TO 600' & PUMPED 40 SX CMT. 4TH PLUG PULL UP TO 230' & PUMP 40 SX CMT. 5TH PLUG PULL TO 40' AND PUMP 10 SX CMT.

RECEIVED  
'MAR 29 2002  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 614' OF 4 1/2" CASING.

Plugged through: TBG

District: 01 Signed Kevin D Strube  
(TECHNICIAN)

INVOICED  
DATE March 29-02 MAR 26 2002  
INV. NO. 2002061593  
Form C-20