

15.075.30695.0000

Docket No. D-12,486

1 110018

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 12-7-65
C SW NE, SEC. 13, T 21 S, R 41 W/EX

3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4253

Lease Name Bengston Well # 1-D

Operator: Plains Petroleum Company

County Hamilton 90.77

Name & Address P. O. Box 15278

Well Total Depth 2793 feet

Lakewood, CO 80215

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 391

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Dowell Schlumberger License Number NA

Address P. O. Box 887, Ulysses, KS 67880

Company to plug at: Hour: 3:50 pm Day: 10 Month: January Year: 19 86

Plugging proposal received from Steve Steele

(company name) Plains (phone) 316-355-7122

were: 2 7/8" at 2497' PBTD 2465' Perfs at 2364-2375'; 2432-2448'

Run 1-1/4" line pipe of tubing down to the perforations and pull back out of hole spotting cement plugs in such a fashion as to fill the 2-7/8" disposal string with cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1986

Plugging Proposal Received by Steve Durrant CONSERVATION DIVISION
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 9:00 am Day: 10 Month: January Year: 19 86

ACTUAL PLUGGING REPORT Circulated hole with 1 bbl water through 2394' 1 1/4" pipe. Pumped 5 bbls cement & 1/4 bbls water. Pulled 40 joints to 1554'. Pumped 5 bbls cement. Pulled 42 joints to 672'. Pumped 5 bbls cement. Lost returns. Got returns back. Pulled 24 joints. Circulated cement. Pulled 7 joints. Filled casing with cement. Shut down.

No Recovery.

Remarks: Used 60/40 Pozmix 6% gel by Dowell. Circulated hole from TD ot surface.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 5 1986

Signed James Plann
(TECHNICIAN)

INV. NO. 12321