

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-30094-00-00  
Spot: CNESW Sec/Twnshp/Rge: 14-21S-41W  
1980 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: HCU Well Number: 1411 D  
County: HAMILTON Total Vertical Depth: 6096 feet

Operator License No.: 31321 Conductor Pipe: Size 20 feet: 24  
Op Name: LOUIS DREYFUS NATURAL GAS CORP. Surface Casing: Size 8.625 feet: 2815 WITH 1230 SX CMT  
Address: 14000 QUAIL SPNGS PKWY STE 600 Production: Size 5.5 feet: 6094 WITH 240 SX CMT  
OKLAHOMA CITY, OK 73134 Liner: Size feet: 8198.12

Well Type: SWD UIC Docket No: D11755.0 Date/Time to Plug: 09/18/2001 9:30 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 2325'. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY  
Date/Time Plugging Completed: 09/18/2001 3:00 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: KEVIN STRUBE


Actual Plugging Report:

PBTD 2325'. 5 1/2" CUT OFF AROUND 04/01/65 @ 2833'. TOC @ 3800'. PERFS AT 2763-74'. CIBP @ 2500' MODEL D PACKER @ 2800'. CIBP SET @ 2325' ON 06/01/01. ON 09/17/01 LOADED HOLE WITH MUD & PULLED TUBING & PACKER. ON 09/18/01 RAN 2 3/8" TUBING IN HOLE TO 2320' PUMPED 15 SX CMT. PULLED TUBING TO 1200' & PUMPED 40 SX CMT. PULLED TUBING TO 600' & PUMPED 35 SX CMT. PULLED TUBING TO 40' & PUMPED 10 SX CMT.

Remarks: USED COMMON CEMENY BY SARGENTS. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed   
(TECHNICIAN)

RECEIVED  
SEP 25 2001  
KCC WICHITA

INVOICED  
DATE 9-25-01  
INV. NO. 2002060610

SEP 24 2001

  
Form CP-23

