

11100307

TO: STATE CORPORATION COMMISSION

API NUMBER 15-075-30,019-0000
C NW NW SEC. 14, T 21 S, R 41 W

10-01

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HCU WELL # 1411-B

TECHNICIAN'S PLUGGING REPORT

COUNTY HAMILTON

OPERATOR LICENSE # 31321

WELL TOTAL DEPTH 2788 FEET

40.61

OPERATOR: LOUIS DREYFUS NATURAL GAS PRODUCTION CSG: SIZE 5 1/2" @ 2788 WITH 100 SX

NAME AND 14000 QUAIL SPRINGS PKWY #600 SURFACE CASING: SIZE 8 5/8" @ 314' WITH 300 SX

ADDRESS OKLAHOMA CITY, OK 73134

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 30 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 2766-2774

TOP OF CEMENT AT 2350'. 1ST PLUG SPOT 25 SX CEMENT WITH 200# HULLS AT 2766' TO 2566'.

2ND PLUG SPOT 20 SX CEMENT AT 1200' DOWN 1 1/2" TUBING. 3RD PLUG SPOT 50 SX CEMENT AT 350'

DOWN 1 1/2" TUBING. 4TH PLUG SPOT 10 SX CEMENT FROM 40' TO 0'. CEMENT AT 3' DOWN AND HELD.

INVOICED

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

DATE 10-26-99 PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED 10-23-99 HOUR: 1:00 PM DAY: 01 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT

TOP OF CEMENT AT 2350'. 1ST PLUG SPOT 25 SX CEMENT WITH 200# HULLS AT 2766' TO 2566'.

2ND PLUG SPOT 20 SX CEMENT AT 1200' DOWN 1 1/2" TUBING. 3RD PLUG SPOT 50 SX CEMENT AT 350'

DOWN 1 1/2" TUBING. 4TH PLUG SPOT 10 SX CEMENT FROM 40' TO 0'. CEMENT AT 3' DOWN AND HELD.

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 1999 10-12-99

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 1202' OF 5 1/2" CASING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters
(TECHNICIAN) FORM CP-2/3

[Handwritten signature and initials]