

To: 1 080075 15.075.20103.0000  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- Docket #D-19,058  
C SW NE, SEC. 6, T 21 S, R 40 W/4  
3300 feet from S section line  
1980 feet from E section line

10-22

TECHNICIAN'S PLUGGING REPORT

Operator License # 3871  
Operator: Hugoton Energy Corp.  
Name:  
Address -301 N. Main, Ste. 1900  
Wichita, KS 67202

Lease Name Adams Well # 1  
County Hamilton 92.36  
Well Total Depth 2842 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well  D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: 9:30 a.m. Day: 22 Month: 10 Year: 19 96

Plugging proposal received from Joe Brougher

(company name) Hugoton Energy Corp. (phone) 316-277-0803

work: 4 1/2" at 2842' w/500 sx cement, PBTD 2800', Perfs at 2396-2478'

1st plug pump 5 sx hulls and 100 sx cement,

2nd plug pressure up backside and pump 50 sx cement if necessary. 10-29-96

RECEIVED  
KANSAS CORPORATION  
OCT 29 1996  
P 3 11

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30 a.m. Day: 22 Month: 10 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped down 8 5/8" X 4 1/2" with 20 sx cement. Shut in pressure 200#.

2nd plug pumped down 4 1/2" with 150 lbs. hulls and 150 lbs. hulls mixed in first 25 sx of a total of 110 sx cement.

Maximum pressure 400 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 10-31-96

Signed Kevin D. Stuch (TECHNICIAN)

INV. NO. 46871