

1 110030

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 075-20,110 -0000

C NW SE, SEC. 3, T 21 S, R 40 W/E

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4742

Lease Name Grilliot Well # 2

Operator: Texaco, Inc.

County Hamilton 92.63

Name & Address 1013 S. Kansas

Well Total Depth 2850 feet

Liberal, KS 67901

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 321

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Dowell Schlumberger License Number N/A

Address P. O. Box 1551, Liberal, KS 67901

Company to plug at: Hour: 10:30 am Day: 21 Month: March Year: 1986

Plugging proposal received from Johnny Robertson

(company name) Texaco, Inc. (phone) 405-696-2291

were: 4 1/2" at 2850' PRTD 2835' Perfs at 2807-2812' Cement Circulated

Pump through tubing with mud between plugs

1st plug pump 15 sx cement and 1 sack hulls at perfs

2nd plug at 2400' with 20 sx cement 3rd plug at 1500' with 30 sx cement
solid bridge - hulls plug at 40'

4th plug at 350' with 10 sx cement 5th plug cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:00 pm Day: 21 Month: March Year: 1986

ACTUAL PLUGGING REPORT Circulated hole through 2804' tubing 1 sack hulls with gel pumped 15

sx cement. Pulled tubing to 2380' and pumped 20 sx cement, pulled to 1498' and pumped 30

sx cement, pulled to 351' and pumped 10 sx cement. Pulled to 32' and pumped 4 sx cement.

Pulled pipe and filled casing to ground level with cement.

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Dowell.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did, did not) observe this plugging.

DATE APR 1 1986

STATE CORPORATION COMMISSION

Signed James P. K...
(TECHNICIAN)

INV. NO. 13218

MAR 31 1986

3-21

CONSERVATION DIVISION