

1031519

TO: STATE CORPORATION COMMISSION

4-21

API NUMBER 15-075-20,698-0000
NE NW SW SEC. 34, T 21 S, R 39 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HARVEY WELL # 12-34

TECHNICIAN'S PLUGGING REPORT COUNTY HAMILTON

OPERATOR LICENSE # 32059 WELL TOTAL DEPTH 5400 175.50 FEET

OPERATOR: GULF PRODUCTION CORP. PRODUCTION CSG: SIZE @ ' WITH SX

NAME AND 9701 N BROADWAY SURFACE CASING: SIZE 8 5/8" @ 372' WITH SX

ADDRESS OKLAHOMA CITY, OK 73114

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MURFIN DRILLING LICENSE NUMBER 30606

ADDRESS 250 N WATER, SUITE 300, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 6:00 AM DAY: 21 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM GUS

(COMPANY NAME) MURFIN DRILLING (PHONE) 316-267-3241

WERE:

1ST PLUG AT 2300' WITH 50 SX CEMENT. 2ND PLUG AT 1290' WITH 80 SX CEMENT.

3RD PLUG AT 390' WITH 50 SX CEMENT. 4TH PLUG AT 0-40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RATHOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSEHOLE WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 8:45 AM DAY: 21 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 2300' WITH 50 SX CEMENT. 2ND PLUG AT 1290' WITH 80 SX CEMENT.

3RD PLUG AT 390' WITH 50 SX CEMENT, 4TH PLUG AT 0-40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT.

6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY HALLIBURTON

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID NOT) OBSERVE THIS PLUGGING.

DATE MAY 19 1999

MAY 10 1999

SIGNED

Steve Durrant (TECHNICIAN)

FORM CP-2/3

CONSERVATION DIVISION Kansas

5-10-99