

To: 1 090667  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION App.  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-075-20,580-0000  
SW NE SE, SEC. 31, T 21 S, R 39 W/E  
1500 feet from S section line  
800 feet from E section line

4-6

TECHNICIAN'S PLUGGING REPORT

Operator License / 5952  
Operator: Amoco Production Company  
Name:  
Address P.O. Box 800, Room 924  
Denver, CO 80201

Lease Name Silverheels Well # 1-31  
County Hamilton  
Well Total Depth 5425 <sup>1763)</sup> feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 493

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A  X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382  
Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: \_\_\_\_\_ Day: 6 Month: 4 Year: 19 96

Plugging proposal received from Jack Pepper  
(company name) Cheyenne Drilling, Inc. (phone) 316-277-2062

Work: to fill hole with heavy mud and spot cement through drill pipe  
1st plug at 2330' with 50 sx cement, 2nd plug at 1150' with 80 sx cement,  
3rd plug at 620' with 50 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

RECEIVED  
KANSAS CORP  
COMM  
1996 APR 15 4 17

4-15-96

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 5:15 p.m Day: 6 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 2333' with 50 sx cement,  
2nd plug at 1150' with 80 sx cement,  
3rd plug at 640' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)  
I (XXX / did not) observe this plugging.

INVOICED  
DATE APR 18 1996

INV. NO. 45338  
4-6

Signed [Signature]  
(TECHNICIAN)

