

To: 1 020810 10-21  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION W/2  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 075-20,545-0000  
W/2 SE, SEC. 32, T. 21 S, R. 39 W/2

1320 feet from S section line

2500 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Lease Name Barker Well # 1-32

Operator: Amoco Production Company

County Hamilton

Name & Address P.O. Box 800, Room 925

Well Total Depth 3473 112.87 feet

Denver, CO 80201

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 2359

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton License Number \_\_\_\_\_

Address Liberal, KS

Company to plug at: Hour: 11 a.m. Day: 21 Month: 10 Year: 19 94

Plugging proposal received from Spanky

(company name) Halliburton (phone) 800-853-3555

were: 5 1/2" at 3473' w/465 sx cement, PBD 3240', Perfs at 2762-3324' (8 sets)

1st plug pump 2 sx hulls and 158 sx cement to perfs, pressure, displace to 950',

2nd plug tag wiper plug, perforate, circulate cement to surface.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:45 p.m. Day: 21 Month: 10 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 158 sx cement to perfs, pressured to

1500# with wiper plug, displaced to 950',

2nd plug tagged wiper plug at 870', perforated at 850', circulated cement to surface with

169 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 31 1994

Remarks: Used 65/35 Lite Class C cement with 6% gel by Halliburton. No casing recovered

(If additional description is necessary, use BACK of this form.)

INVOICED  
(If applicable) observe this plugging.

DATE 11-2-94

INV. NO. 41553

Signed Glenn R Barlow  
(TECHNICIAN)