

1080283

TO: STATE CORPORATION COMMISSION

API NUMBER 15-075-00127-0000
SE NW SEC. 36, T 21 S, R 41 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HCU WELL # 3611

TECHNICIAN'S PLUGGING REPORT COUNTY HAMILTON 90.68

OPERATOR LICENSE # 31321 10-27 WELL TOTAL DEPTH 2790 FEET

OPERATOR: LOUIS DREYFUS NATURAL GAS PRODUCTION CSG: SIZE 4 1/2" @ 2790' WITH 500 SX

NAME AND 14000 QUAIL SPRINGS PKWY STE 600 SURFACE CASING: SIZE 7 5/8" @ 193' WITH 200 SX

ADDRESS OKLAHOMA CITY, OK 73134

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 10:20 AM DAY: 27 MONTH: 10 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 2746-56

SHOT 2 7/8 AT 2536' PACKER LEFT IN HOLE. CUP TYPE PACKER AT 2665'. PUMPED 20 SX CEMENT

WITH 75# HULLS AT 2506'. PULLED TUBING UP TO 1300' PUMPED 75 SX CEMENT. WELL CIRCULATING

TO SURFACE, PULLED TUBING UP TO 332' PUMPED 20 SX CEMENT. PULLED OUT OF HOLE TOPPED OFF

WITH 5 SX CEMENT. PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 27 MONTH: 10 YEAR: 1999

ACTUAL PLUGGING REPORT

SHOT 2 7/8 AT 2536' PACKER LEFT IN HOLE. CUP TYPE PACKER AT 2665' PUMPED 20 SX CEMENT WITH

75# HULLS AT 2506'. PULLED TUBING UP TO 1300' PUMPED 75 SX CEMENT. WELL CIRCULATING TO

SURFACE. PULLED TUBING UP TOP 332' PUMPED 20 SX CEMENT. PULLED OUT OF HOLE TOPPED OFF

WITH 5 SX CEMENT. 7 5/8" X 4 1/2" ANNULUS FULL OF CEMENT AT SURFACE. STATE CORPORATION COMMISSION

11-2-99 NOV - 2 1999

REMARKS: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING. DATE 12/3

DATE 12/3

SIGNED Kevin D. Strube

(TECHNICIAN) FORM CP-2/3

INV. NO. 60890

Handwritten initials and a circled 'R'.