

1080226

TO: STATE CORPORATION COMMISSION

10-21

API NUMBER 15-075-10,016-0000
C NE SW SEC. 34, T 21 S, R 41 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HCU (FRAZIER) WELL # 3411

TECHNICIAN'S PLUGGING REPORT

COUNTY HAMILTON 91.00

OPERATOR LICENSE # 31321

WELL TOTAL DEPTH 2800 FEET

OPERATOR: LOUIS DREYFUS NATURAL GAS PRODUCTION CSG: SIZE 4 1/2" @ 2799' WITH 100 SX

NAME AND 14000 QUAIL SPRINGS PKWY STE 600 SURFACE CASING: SIZE 8 5/8" @ 170' WITH 125 SX

ADDRESS OKLAHOMA CITY, OK 73134

ABANDONED OIL WELL GAS WELL X INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

10-30-98

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 21 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MANNY BOATWRIGHT

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

10-30-98

WERE: PERFS AT 2748'

1ST PLUG SHOT CASING AT 1170' PIPE NOT FREE. PUMPED DOWN 4 1/2" 60 SX CEMENT. DISPLACED TO 800' 4 1/2" ON VACUUM LET SET 30 MIN. PUMPED ON 4 1/2" STILL MOVING LET SET 1 1/2 HOURS. PRESSURED UP TO 100#. 2ND PLUG SHOT CASING AT 798' PULLED UP TO 500' PUMPED 50 SX CEMENT. 3RD PLUG PULLED UP TO 200' PUMPED 45 SX CEMENT CIRCULATED TO SURFACE. PULLED OUT OF HOLE 8 5/8" STAYED LOADED WITH CEMENT TO SURFACE. PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 21 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT JUNK IN HOLE. TUBING FISH APP. 1500'. RAN IN HOLE FOUND TOP AT 1200'. 1ST PLUG SHOT CASING AT 1170' PIPE NOT FREE. PUMPED DOWN 4 1/2" CASING 60 SX CEMENT. DISPLACED TO 800' 4 1/2" ON VACUUM LET SET 30 MIN.. PUMPED ON 4 1/2" STILL MOVING LET SET 1 1/2 HRS. PRESSURED UP TO 100#. 2ND PLUG SHOT CASING AT 798' PULLED UP TO 500' PUMPED 50 SX CEMENT. 3RD PLUG PULLED UP TO 200' PUMPED 45 SX CEMENT CIRCULATED TO SURFACE. PULLED OUT OF HOLE 8 5/8" STAYED LOADED WITH CEMENT TO SURFACE.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 798' OF 4 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin D Strub (TECHNICIAN) FORM CP-2/3

11-2-98
60237