

TO: 1-080203

6-25

API NUMBER SPUD 1964

STATE CORPORATION COMMISSION C-NW-SE SEC 30, T 21 S, R 41 W  
 CONSERVATION DIVISION - PLUGGING SECTION 1980' FEET FROM SOUTH SECTION LINE  
 WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980' FEET FROM EAST SECTION LINE  
 WICHITA, KANSAS 67202 LEASE NAME L.H. HATFIELD WELL# 1  
 TECHNICIAN'S PLUGGING REPORT COUNTY HAMILTON  
 OPERATOR LICENSE # 30385 WELL TOTAL DEPTH 2780' FEET  
 OPERATOR: LIEDTKE OPERATING CORP. PRODUCTION CSG: SIZE 4 1/2 FEET 2779'  
 NAME AND 475 17th ST, STE 960 SURFACE CASING: SIZE 8 5/8 FEET 385'  
 ADDRESS DENVER CO. 80202

90,35

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SUPERIOR SERV. INC. LICENSE NUMBER 32297

ADDRESS P.O. BOX 772, LIBERAL, KS 67905-0772

COMPANY TO PLUG AT: HOUR: 9:00am DAY: 25 MONTH: 6 YEAR: 98 Wichita, Kansas

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) RICHARD TENNANT (PHONE) (316)-587-3700

WERE: RUN TUBING TO 2700', PUMPED 25 SX CEMENT WITH 100 LBS HULLS, PULL CASING UP TO 1200', PUMP 50 SX CMT, PULL UP TO 410, PUMP 50 SX CMT, PULL UP TO 40', CIRCULATE TO SURFACE

PLUGGING PROPOSAL RECEIVED BY Kevin Strube

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 8:30PM DAY: 25 MONTH: 6 YEAR: 98

ACTUAL PLUGGING REPORT PERFORATIONS AT 2760-72 RAN TUBING TO 2700, ALLIED PUMPED 25 SX CEMENT WITH 100 LBS HULLS, LK WIRELINE PERFORATED AT 1200', RUN TUBING IN HOLE TO 1200', ALLIED PUMPED 40 SX CEMENT, PULLED TUBING, LK RAN FREE POINT ON 4 1/2 CASING, FOUND AT 800', LK RAN CASING CUTTER TO 785, CUT CASING, PULLED CASING OUT OF HOLE, RAN TUBING TO 765, PUMPED 50 SX, PULLED UP TO 410, PUMPED 40 SX, PULLED UP TO 40', PUMPED 15 SX

REMARKS: Used 60/40 Pozmix 6% gel by ALLIED

casing recovery 785'

I (DID/xxxxxxx) OBSERVE THIS PLUGGING.

SIGNED

*Kevin P. Strube*  
(TECHNICIAN)

FORM CP-2/3

INVOICED

DATE JUL 13 1998

INV. NO. 50903

RECEIVED  
 STATE CORPORATION COMMISSION  
 7-10-98  
 JUL 10 1998  
 CONSERVATION DIVISION  
 Wichita, Kansas