

1080324

TO: STATE CORPORATION COMMISSION

API NUMBER 15-075-10,025-0000  
C NW SE SEC. 29, T 21 S, R 41 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HCU WELL # 2911

TECHNICIAN'S PLUGGING REPORT 8/3 COUNTY HAMILTON 91.16

OPERATOR LICENSE # 31321 WELL TOTAL DEPTH 2805 FEET

OPERATOR: LOUIS DREYFUS NATURAL GAS PRODUCTION CSG: SIZE 4 1/2" @ 2804' WITH 100 SX

NAME AND 14000 QUAIL SPRINGS STE. 600 SURFACE CASING: SIZE 8 5/8" @ 137' WITH 125 SX

ADDRESS OKLAHOMA CITY, OK 73134

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 03 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 2775' HOLE IN 4 1/2" @ 1551-61.

ON 8/2/00 PUMP DOWN 2 7/8" TUBING WITH 200# HULLS & 20 SX CEMENT. SHOT CASING AT 1217'.

1ST PLUG PULL UP TO 1187' LOADED HOLE WITH MUD. HAD CIRCULATION TO SURFACE PUMPED 80 SX

CEMENT. 2ND PLUG PULL UP TO 750' PUMPED 50 SX CEMENT DISPLACED WITH MUD.. 3RD PLUG PULL

UP TO 200' PUMP 50 SX CEMENT DISPLACED WITH MUD. 4TH PLUG PULL UP TO 40' PUMP 10 SX

CEMENT AT SURFACE. PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 6:00 PM DAY: 03 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

ON 8/2/00 PUMPED DOWN 2 7/8" TUBING WITH 200# HULLS & 20 SX CEMENT. SHOT CASING AT 1217'.

1ST PLUG PULL UP TO 1187' LOAD HOLE WITH MUD. HAD CIRCULATION TO SURFACE PUMPED 80 SX

CEMENT. 2ND PLUG PULL TO 750' PUMP 50 SX CEMENT DISPLACED WITH MUD. 3RD PLUG PULL UP TO

750' PUMP 50 SX CEMENT DISPLACED WITH MUD. 4TH PLUG PULL UP TO 200' PUMP 50 SX CEMENT

DISPLACED WITH MUD. 4TH PLUG PULL UP TO 40' PUMP 10 SX CEMENT AT SURFACE.

REMARKS: USED COMMON CEMENT BY SARGENT'S RECOVERED 1217' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

AUG 14 2000

DATE 8/2/00

SIGNED

*Kevin D. Strube*  
(TECHNICIAN)

FORM CP-2/3

CONSERVATION DIVISION  
Wichita, Kansas

FILE NO. 106044