

2-070368

168  
R

S-13

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-159-20,468-0000

SE, SECTION 18 TOWNSHIP 21 RANGE 7W

OPERATOR LICENSE # 4424 550 FEET FROM S SECTION LINE  
1840 FEET FROM E SECTION LINE

OPERATOR Smokey Valley Resources  
NAME & Box 165  
ADDRESS McPherson, KS 67460

LEASE NAME: Ball #3  
COUNTY: Rice

WELL TOTAL DEPTH: 3407' 110.72

CONDUCTOR PIPE: " @ '  
SURFACE CASING: 8-5/8" @ 207'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SUD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Sunflower Well Service  
ADDRESS: Canton, KS LICENSE: 30280

COMPANY TO PLUG AT: HOUR: pm DAY: 10 MONTH: 5 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Bud Davis

COMPANY NAME: Sunflower Well Service PHONE: 316-628-4723

WERE: 5-1/2" @ 3392' - open hole to 3407' - sand to 3346' - cap w/5 sx - recover available pipe - circ 35 sx cmt @ 975+ and 400' to surface.

PLUGGING PROPOSAL RECEIVED BY: Merlan Unruh

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 6:30 DAY: 13 MONTH: 5 YEAR: 1991

ACTUAL PLUGGING REPORT:  
Sand to 3346' - capped w/5 sx cmt by bailer - shot pipe @ 2532' - pulled pipe to 970' - circ 35 sx cmt - pulled pipe to 400' - circ to surface.

RECEIVED  
STATE CORPORATION COMMISSION

REMARKS: Allied #1340 60/40 4%

MAY 22 1991

I DID OBSERVE THIS PLUGGING.

CONSERVATION DIVISION  
Wichita, Kansas

Jack Luthi  
Jack Luthi (AGENT)

FORM CP-2/3  
REV. 3/90

INVOICED

DATE 5-29-91

INV. NO. 31951

aw