

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

2-090551

API Number: 15-159-20,203-0000

C SE SE SECTION 18 TWP 21 RANGE 07W

OPERATOR LICENSE #5920 FEET FROM S SECTION LINE 660
OPERATOR TE-PE OIL AND GAS FEET FROM E SECTION LINE 660
NAME & P.O. BOX 522
ADDRESS CANTON, KS 67428

LEASE NAME BALL #1
COUNTY RICE
WELL TOTAL DEPTH 3440' 111,80
PIPE 4 1/2" @ 3439'
SURFACE CASING 8 5/8" @ 250'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING AND SALVAGE

ADDRESS: P.O. BOX 457, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: _____ HOUR: 8:00 DAY: 22 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: MIKE

COMPANY NAME: MIKES TESTING AND SALVAGE PHONE: (316) 938-2537

WERE: SAND TO 3200'. CAP WITH 4 SACKS OF CEMENT. SHOOT PIPE FOR RECOVERY.

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 03 1998

PLUGGING PROPOSAL RECEIVED BY: RALPH TITTEL CONSERVATION DIVISION
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE 11-3-98

COMPLETED: HOUR: 16:30 DAY: 26 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT: SANDED TO 3200'. CAP WITH 4 SACKS OF CEMENT. RECOVERED 1000' OF 4 1/2".
THROUGH CASING SPOT 35 SACKS @ 1000', 35 SACKS @ 650. CIRCULATE FROM 300' TO SURFACE.

REMARKS: ALLIED 160 SACKS - 60/40 POZ, 4% GEL.

I DID OBSERVE THIS PLUGGING.

Ralph Tittel
RALPH TITTEL

FORM CP-2/3
REV. 3/90

60262