

5 030524

8-25 15.113.05975.0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- N/A  
SE NE SE, SEC. 32, T 21 S, R 3 W/EX  
1650 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5350  
Operator: Brunson Production  
Name & Address: 125 N. Emporia, #200  
Wichita, KS 67202

Lease Name Schroeder Well # 3  
County McPherson 112.45  
Well Total Depth 3460' feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8-5/8 feet 287' w/225 SX

Abandoned Oil Well X Gas Well Input Well SWD Well D&A  
Other well as hereinafter indicated

Plugging Contractor Tom Brown Construction License Number  
Address Lindsborg, KS

Company to plug at: Hour: 10:00 Day: 25 Month: 8 Year: 19 89

Plugging proposal received from Elmer Hauser

(company name) Brunson Production (phone) 316-662-0172

were: 5-1/2" @ 3436' w/100 sx - perforations - squeezed @ 1807-39' with 60 sx  
cement - perfs 940-60' w/90 sx cement - perfs 290'-380' w/150 sx - cement  
(circ to surface then close & squeeze)

Run tubing in hole to bottom - circ 50 sx cement - pull tubing out of cmt &  
circ gel to 400' - pull tubing to 400' & circ cement to surface - check csg

Plugging Proposal Received by Dist #2 (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:00 Day: 25 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT No casing recovery - cmt circ to surface from

perfs 290'-380' & squeezed - ran tubing in hole & circ 50 sx cmt on bottom -  
pulled 19 jts - circ 25 sx gel w/150# hulls - pulled tub to 390' (13 jts in hole)  
& circ cmt to surface w/50# hulls - pulled tubing - refilled hole - hooked up to  
5-1/2" - 8-5/8" annulus & checked - full - used 100 sx 60/40 poz, 25" sx gel, 200# hulls.  
Howco #796241-6 B-843233

Remarks: (If additional description is necessary, use BACK of this form.)  
Wichita, Kansas

SEP 13 1989  
9-13-89

INVOICED

DATE 9-18-89  
INV. NO. 25893  
8-25

WC

Signed Merlan Lussak (TECHNICIAN)