

2-22-88 15.159.20454.0000

5 020401

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-20, V54
NE, SEC. 20, T. 21 S, R 7 W/EX
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142
Operator: Sterling Drilling Company
Name & Address Box 129
Sterling, KS 67579

Lease Name Nims Well # 1
County Rice 111.51
Well Total Depth 3431 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 182

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, Kansas

Company to plug at: Hour: 11:00am Day: 22 Month: 2 Year: 1988

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling (phone) _____

were: Fill hole with sand to 3360' and cement with 5 sxs cement. Set rock bridge
(on fluid) from 380'-360' and cement hole to base of cellar with 6 yards
redimix concrete.

Plugging Proposal Received by Gilbert J. Toman
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45pm Day: 22 Month: 2 Year: 1988

ACTUAL PLUGGING REPORT Hole filled with sand to 3360' and cemented with 5 sxs cement.
Rick bridge set (on fluid) from 380'-360' and hole cemented to base of
cellar with 6 yards redimix concrete.

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1 1988

5 1/2" @3420 2600' of 5 1/2" casing recovered

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Mid America Redimix #3150
(If additional description is necessary, use BACK of this form.)

INVOICED

(could not) observe this plugging.

Signed Gilbert J. Toman pd
(TECHNICIAN)

DATE 3-14-88
INV. NO. 20100