

1 051112

12-20
API NUMBER 15-145-20.367-0000

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE/4, SEC. 24, T 21 S, R 18 W EX

3960 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Beer Well # 1-24

Operator: Benson Mineral Group, Inc.

County Pawnee 70.20

Name & Address 1536 Cole Blvd., Suite 220

Well Total Depth 2160 feet

Golden, CO 80401

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 839

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 20 Month: 12 Year: 19 88

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 2159' PBTD 2100' Perfs at 2081-87', 2063-73'

1st plug sand back to 2010' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1988

Plugging Proposal Received by Stephen J. Pfeifer
(TECHNICIAN)

12-22-88

Plugging Operations Attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 20 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 2010' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1667' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOLVED
I (or) ~~we~~ observe this plugging.

DATE DEC 22 1988

Signed Richard W. Lucas
(TECHNICIAN)

INV. NO. 23426