

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20615-00-00
Spot: CSE Sec/Twnshp/Rge: 21-21S-40W
1250 feet from S Section Line, 1250 feet from E Section Line
Lease/Unit Name: PETTIT A Well Number: 2-21
County: HAMILTON Total Vertical Depth: 2864 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

Conductor Pipe: Size feet: 893.08
Surface Casing: Size 8.625 feet: 337 WITH 225 SX CMT
Production: Size 4.5 feet: 2864 WITH 750 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/23/2002 10:50 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP 5 SX HULLS FOR PLUG, 150 SX 60/40 POZ MIX W/6 % GEL. PRESSURE UP ON BACKSIDE (8-5/8" X 4-1/2") & PUMP 50 SX DOWN ANNULUS, IF NECESSARY/

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/23/2002 11:35 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:
PBTD 2863'. PERFS AT 2840-45'. PUMPED DOWN 4 1/2" WITH 400# HULLS & 155 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN AT 800#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 15 SX CMT. MAXIMUM PRESSURE 500#. SHUT IN AT 300#.

RECEIVED
JAN 31 2002
KCC WICHITA
1-31-02

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin D Strube
(TECHNICIAN)

INVOICED JAN 29 2002
DATE Feb. 1-02
INV. NO. 2002061326

Form CP 2/3